

ANNEXURE - I I

RAMAGUNDAM MUNICIPAL CORPORATION: DIST: PEDDAPALLI

Name of the work: Supply of Erection for 160 KVA DG Set with Standard Control Panel in
Ramagundam Municipal Corporation

Sl.no.	Description of work /Item	Qty	Rate	Per
1	Supply, Transportation, unloading and installation of the 160 KVA DG Set at your site	1		1 Job
2	Laying of CC foundation bed including materials and labor (L-16FT."W-8 FT"D-2 FT)	1		1 Job
3	Supply and laying of 240 sq mm 3 1/2 core e aluminum armound cable	120		Mts
4	Supply and fixing of 300 amps 4 pole changeover switch of standard brand	1		1 Job
5	Excavation digging for earthing of DG Set with GI pipe of suitable length with GI strips including material like charcoal, salt etc and refilling	2		2 nos
6	Excavation digging for earthing of DG Set with GI pipe of suitable length with copper strips of suitable length and dimensions including material etc.,	2		2 nos
7	Hardware like Glands, Lugs, Washers, Nut Bolts etc.,	1		1 Job
8	Exhaust pipe extension with cladding	1		1 Job
9	Diesel for testing and commissioning of DG set including transportation and handling charges	200		Ltrs
10	Manufacture supply and erection of rain protection steel sheet shed of suitable length and width with necessry hardware fitting etc.,	1		1 Job
11	Erection charges for under taking the above works	1		1 Job